SECTION III B-SCHEDULE OF RATES-4 BAR

RATE CONTRACT FOR SUPPLY OF VARIOUS SIZES OF 4 BAR RPD INDUSTRIAL METERING SKIDS (IMS) ACROSS GEL LOCATIONS OF GUJARAT, DADRA AND NAGAR HAVELI (DNH), PALGHAR DISTRICT AND THANE RURAL, PUNJAB, HARYANA, RAJASTHAN AND MADHYA PRADESH

Tender ID – 360298

Sr. No.	Material code	Item Description	UOM	Qty (Nos.)	Unit Rate (Rs.)	Total Basic Value (Rs.)	GST (In Percentage)	GST (In Rs)	Unit Rate with GST (Rs.)	Total Amount (Rs.)
1	100012702	IMS,G16,RPD,250SCMH,2",150#,W/FRP,CANPY Design, Engineering, Manufacturing, Inspection & Testing, FAT,SAT Supply of Above ground Industrial Metering Skid (IMS 250 SCMH-150#) along with FRP Canopy containing Filter with DPG, PG, NRV, Strainer, Transition Fitting and G16 RPD Meter. GGL will free issue Meter and Installation of Meter is in Vendor scope.	EA	120						
2	100012703	IMS,G25,RPD,250SCMH,2",150#,W/FRP,CANPY Design, Engineering, Manufacturing, Inspection & Testing, FAT,SAT Supply of Above ground Industrial Metering Skid (IMS 250 SCMH-150CLASS) along with FRP Canopy containing Filter with DPG, PG, NRV, Strainer, Transition Fitting and G25 RPD Meter. GGL will free issue Meter and Installation of Meter is in Vendor scope.	EA	30						
3	100012704	IMS,G40,RPD,250SCMH,2",150#,W/FRP,CANPY Design, Engineering, Manufacturing, Inspection & Testing, FAT,SAT Supply of Above ground Industrial Metering Skid (IMS 250 SCMH-150#) along with FRP Canopy containing Filter with DPG, PG, NRV, Strainer, Transition Fitting and G40 RPD Meter. GGL will free issue Meter and Installation of Meter is in Vendor scope.	EA	40						
4	100012705	IMS,G65,RPD,250SCMH,2",150#,W/FRP,CANPY Design, Engineering, Manufacturing, Inspection & Testing, FAT,SAT Supply of Above ground Industrial Metering Skid (IMS 250 SCMH-150#) along with FRP Canopy containing Filter with DPG, PG, NRV, Strainer, Transition Fitting and G65 RPD Meter. GGL will free issue Meter and Installation of Meter is in Vendor scope.	EA	30						
5	100012706	IMS,G100,RPD,500SCMH,3",150#,W/FRP,CANPY Design, Engineering, Manufacturing, Inspection & Testing, FAT,SAT Supply of Above ground Industrial Metering Skid (IMS 500 SCMH-150#) along with FRP Canopy containing Filter with DPG, PG, NRV, Strainer, Transition Fitting and G100 RPD Meter. GGL will free issue Meter and Installation of Meter is in Vendor scope.	EA	10						
6	100012707	IMS,G160,RPD,500SCMH,3",150#,W/FRP,CANPY Design, Engineering, Manufacturing, Inspection & Testing, FAT,SAT Supply of Above ground Industrial Metering Skid (IMS 500 SCMH-150#) along with FRP Canopy containing Filter with DPG, PG, NRV, Strainer, Transition Fitting and G160 RPD Meter. GGL will free issue Meter and Installation of Meter is in Vendor scope.	EA	10						
7	100012708	IMS,G250,RPD,750SCMH,3",150#,W/FRP,CANPY Design, Engineering, Manufacturing, Inspection & Testing, FAT,SAT Supply of Above ground Industrial Metering Skid (IMS 750 SCMH-150#) along with FRP Canopy containing Filter with DPG, PG, NRV, Strainer, Transition Fitting and G250 RPD Meter. GGL will free issue Meter and Installation of Meter is in Vendor scope.	EA	5						
8	100012709	IMS,G400,RPD,1500SCMH,4",150#,W/FRPCANPY Design, Engineering, Manufacturing, Inspection & Testing, FAT,SAT Supply of Above ground Industrial Metering Skid (IMS 1500 SCMH-150#) along with FRP Canopy containing Filter with DPG, PG, NRV, Strainer, Transition Fitting and G400 RPD Meter. GGL will free issue Meter and Installation of Meter is in Vendor scope.	EA	5						
9	100012710	IMS,G650,RPD,2000SCMH,6",150#,W/FRPCANPY Design, Engineering, Manufacturing, Inspection & Testing, FAT,SAT Supply of Above ground Industrial Metering Skid (IMS 2000 SCMH-150#) along with FRP Canopy containing Filter with DPG, PG, NRV, Strainer, Transition Fitting and G650 RPD Meter. GGL will free issue Meter and Installation of Meter is in Vendor scope.	EA	5						

Notes:

1. Size wise Two separate SORs have been published. Each SOR is optional to quote, however; it is mandatory to quote non-zero rate for the above mentioned SOR items failing to which bid shall be rejected.
2. Rates quoted by bidder shall be inclusive of door delivery up to GEL store, Packing and Forwarding, Loading and Unloading Charges, Freight, Transit Insurance.
3. Commercial Bid evaluation will be done on individual Line item basis of respective SOR.
4. Quantities mentioned above are estimated quantities for the duration of 18 Months. Separate call-out order shall be issued based on actual requirement and payment shall be made against call-out order.
5. Appointment of Third Party Inspection Agency shall be in the scope of GEL. Bidder shall provide intimation to GEL for Third Party Inspection at least 10 days in advance.

LOCATION WISE BIRFERCATION

Material Code	Description	UoM	Gujarat, DNH & Thane	MP & Rajasthan	Punjab & Haryana	Total
1 BAR RPD Industrial Metering Skids (IMS)						
100013553	IMS,G16,RPD,100SCMH,1BAR,2",W/FRP,CANPY	EA	15	1	4	20
100013554	IMS,G25,RPD,100SCMH,1BAR,2",W/FRP,CANPY	EA	3	1	1	5
100013555	IMS,G40,RPD,100SCMH,1BAR,2",W/FRP,CANPY	EA	3	1	1	5
100013556	IMS,G65,RPD,100SCMH,1BAR,2",W/FRP,CANPY	EA	3	1	1	5
4 BAR RPD Industrial Metering Skids (IMS)						
100012702	IMS,G16,RPD,250SCMH,2",150#,W/FRP,CANPY	EA	100	6	14	120
100012703	IMS,G25,RPD,250SCMH,2",150#,W/FRP,CANPY	EA	22	4	4	30
100012704	IMS,G40,RPD,250SCMH,2",150#,W/FRP,CANPY	EA	30	4	6	40
100012705	IMS,G65,RPD,250SCMH,2",150#,W/FRP,CANPY	EA	25	2	3	30
100012706	IMS,G100,RPD,500SCMH,3",150#,W/FRP,CANPY	EA	8	1	1	10
100012707	IMS,G160,RPD,500SCMH,3",150#,W/FRP,CANPY	EA	8	1	1	10
100012708	IMS,G250,RPD,750SCMH,3",150#,W/FRP,CANPY	EA	3	1	1	5
100012709	IMS,G400,RPD,1500SCMH,4",150#,W/FRPCANPY	EA	3	1	1	5
100012710	IMS,G650,RPD,2000SCMH,6",150#,W/FRPCANPY	EA	3	1	1	5
	TOTAL		**226**	**25**	**39**	**290**

Note :

Primary regions for delivery across various states may be considered as below:

Punjab – Amritsar, Bathinda, Faridkot, Ferozpur, Muktsar, Hoshiarpur, Gurdaspur, Mansa
Haryana – Sirsa, Fatehabad
Rajasthan – Sirohi, Jalore, Banswara, Dungarpur
Madhya Pradesh – Jhabua, Ratlam, Ujjain, Dewas, Indore
Maharashtra – Vasai, Virar, Palghar, Boisar, Dahanu, Thane
Gujarat & DNH - Across State/UT.

Actual delivery location is subject to change as per GGL operational requirement (within particular State/UT) including delivery at site address.